

CITY OF GALENA, ILLINOIS

101 Green Street, PO Box 310, Galena, Illinois 61036



MEMORANDUM

TO: Honorable Mayor Renner and City Council

FROM: Andy Lewis, City Engineer *ALewis*

DATE: 21 May 2019

RE: Grant Park ADA Parking Spaces
Approval of Request for Quotes

Request for quotes for this project were sent to five contractors, of these three responded and are detailed in the attached table and summarized as follows:

Ref #	Company	Base Bid \$
1	Louie's Trenching Service	19,748
2	Wienen Excavating and Landscaping	17,065
3	Dan Sproule Construction	21,050

This project includes the creation of two ADA parking spaces with associated drainage and landscaping work near the Grant Park Pavilion. The project is included in this year's budget with funding from Grant Park Budget (17.52.870.04) and Galena Foundation Project (17.52.890) which respectively contain \$17,500 and \$14,500.

I recommend the city council approves the quote from Wienen Excavating and Landscaping for \$17,065 to create two ADA parking spaces at Grant Park.

Grant Park ADA Parking Spaces - Bid Tabulation

#	Item	Unit	Quantity	Louie's Trenching		Wienen Excavating		Dan Sproule Const.	
				Unit Cost \$	Amount \$	Unit Cost \$	Amount \$	Unit Cost \$	Amount \$
1	Earth excavation, grading	CY	38	80	3040		1450	50	1900
2	Aggregate base, CA-10, 10" thickness, compacted	TON	33	20	660		860	60	1980
3	HMA Pavement, 4" thickness, 2-lifts	TON	21	300	6300		8750	220	4620
4	PCC Sidewalk, 5' wide, 7" thickness, include 6" CA-10 compacted aggregate base, exposed aggregate to match surrounding sidewalk, epoxy dowels at tie-ins	SF	86	18	1548		1310	50	4300
5	French Drain, including trenching, pipe, connections, clean stone and geotextile fabric	LF	20	40	800		650	65	1300
6	Nyloplast drain, 10" diameter, furnish and install, connect to French Drain pipe	SUM	1	600	600		600	1000	1000
7	Pipe Underdrain, 6", solid SDR-35 or Schedule 40, include fittings and connection from French Drain to existing 6" pipe near Pavillion	LF	40	40	1600		1425	50	2000
8	Turf restoration, includes 4" minimum top soil, seed and straw mulch	SF	1000	5	5000		1770	2.35	2350
9	Erosion Control, silt fence	LF	40	5	200		250	40	1600
TOTALS					19748		17065		21050