

# CITY OF GALENA, ILLINOIS

101 Green Street, PO Box 310, Galena, Illinois 61036



## MEMORANDUM

TO: Honorable Mayor Renner and City Council

FROM: Andy Lewis, City Engineer *A Lewis*

DATE: 17 April 2019

RE: Galena River Canoe and Kayak Launch  
Approval of Bids

Bids for this project were sent to six contractors, of which one was returned. This is summarized below and detailed in the attached tabulation.

Contractor	Base Bid \$	Alternate Bid \$
Louie's Trenching Service	127,438.50	5.00

The project involves construction of a canoe and kayak landing ramp, stairs, sidewalk, hand rail, parking lot improvements and associated landscaping. The alternate item was for rock removal at \$0.01 a cubic foot.

The project is presently funded by two grants, one from the Illinois Department of Natural Resources (IDNR) for \$80,000 and another of \$31,580 from the Community Development Fund of Galena (CDFG). The remaining amount of \$15,858.50 is to be discussed by the CDFG with a view to also fund this sum. This will hopefully be confirmed at Monday night's meeting.

Work will commence on the project in late June with completion by the end of September.

I recommend the city council approves the bid from Louie's Trenching Service for \$127,438.50 for the Galena River Canoe and Kayak Launch, contingent on funding from IDNR and CDFG.

**BID TABULATION - FOR LOUIE'S TRENCHING SERVICE**

**GALENA RIVER CANOE AND KAYAK LAUNCH - 2019**

<b>REF. NO.</b>	<b>BID ITEM DESCRIPTION</b>	<b>UNITS</b>	<b>TOTAL</b>	<b>UNIT PRICE</b>	<b>TOTAL COST</b>
1	CLEARING & GRUBBING	LS	1	\$ 1,500.00	\$ 1,500.00
2	EXCAVATION	CY	1583	\$ 9.00	\$ 14,247.00
3	TOPSOIL, THICKNESS 4 INCH (APPROX. 990 SY)	LS	1	\$ 4,950.00	\$ 4,950.00
4	GRANULAR SUBBASE	TON	500	\$ 15.00	\$ 7,500.00
5	CONCRETE STAIRS, AS PER PLAN	LS	1	\$ 6,000.00	\$ 6,000.00
6	HANDRAIL, AS PER PLAN (GALVANIZED)	LF	13.2	\$ 250.00	\$ 3,300.00
7	INLET - PRECAST UNIT	EA	1	\$ 1,500.00	\$ 1,500.00
8	RCP CULVERT, 15"	LF	22.8	\$ 50.00	\$ 1,140.00
9	RCP APRON, 15"	EA	1	\$ 750.00	\$ 750.00
10	ENGINEERING FABRIC	SY	113	\$ 4.00	\$ 452.00
11	STONE RIPRAP	TON	12	\$ 50.00	\$ 600.00
12	HMA, 3 INCH THICK	TON	203	\$ 126.00	\$ 25,578.00
13	CURB & GUTTER	LF	258	\$ 24.00	\$ 6,192.00
14	PCC WALK, 6"	SY	114.1	\$ 90.00	\$ 10,269.00
15	RAMP (INCLUDING TEMPORARY WORKS)	LS	1	\$ 25,000.00	\$ 25,000.00
16	SLIDE RAIL	LS	1	\$ 7,500.00	\$ 7,500.00
17	PAVEMENT MARKINGS, 4" *	LF	423	\$ 1.25	\$ 528.75
18	PAVEMENT MARKINGS, 6" *	LF	65	\$ 1.75	\$ 113.75
19	SIGN & POST, COMPLETE *	EA	1	\$ 250.00	\$ 250.00
20	MULCH, HARDWOOD BARK	SY	40	\$ 30.00	\$ 1,200.00
21	MULCH, STRAW	ACRE	0.18	\$ 6,000.00	\$ 1,080.00
22	SEEDING AND FERTILIZING (CLASS 1B)	ACRE	0.18	\$ 6,000.00	\$ 1,080.00
23	SILT FENCE	LF	227	\$ 4.00	\$ 908.00
24	INLET PROTECTION	EA	1	\$ 300.00	\$ 300.00
25	ORNAMENTAL GRASS, CLUMPS	EA	20	\$ 25.00	\$ 500.00
26	MOBILIZATION	LS	1	\$ 1,000.00	\$ 1,000.00
27	EROSION MOBILIZATION	EA	1	\$ 1,000.00	\$ 1,000.00
28	CONCRETE TESTING	LS	1	\$ 3,000.00	\$ 3,000.00
	<b>TOTAL BASE BID</b>				\$ 127,438.50
	<b>ALTERNATES</b>				
A1	ROCK EXCAVATION	CF	500	\$0.01	\$ 5.00
	<b>TOTAL ALTERNATES</b>				

**NOTES:**

- 1 \* LOCATION TO BE DECIDED BY CITY
- 2 CONTRACTOR MUST SUBMIT A STATEMENT EXPLAINING HOW THE RAMP WILL BE INSTALLED