

REQUEST FOR QUOTES FOR UNIT PRICES 2020

INTRODUCTION AND GENERAL INFORMATION

The City of Galena is requesting quotes for unit prices for a number of work items as detailed on page 2-3 and summarized as follows:

1. Remove and replace sidewalk
2. Remove and replace curb and gutter
3. Remove and replace street surface

The City of Galena may select one or more contractors to complete this work as detailed below. Selection will be based on best value unit price.

SCOPE OF PROJECT

The City of Galena is requesting quotes to complete work detailed below. All work to be in accordance with latest versions of IDOT Standard Specifications for Roads and Bridges, Standard General Conditions of the Construction Contract and City Specifications including Instructions to Bidders and General Requirements (copies available in City Hall).

Exact locations for the proposed work is to be decided at a later date. The city reserves the right to award individual items of work to more than one contractor.

CONDITIONS

All work performed under this contract shall be subject to compliance with the Illinois Prevailing Wage Act, including latest revisions and the Illinois Preference Act. Contractors are required to submit certified copies of their payroll. Contractors must comply with the Drug Free Workplace Act (Source: P.A. 86-1459).

The City of Galena shall be exempt from any liability for costs incurred by unsuccessful bidders in preparation for this proposal.

The City of Galena will receive sealed quotes to complete the proposed work until:

10:00 AM Monday 1st June 2020.

The City of Galena will make payment within thirty (30) days after acceptance of the work. The City of Galena reserves the right to reject any or all quotes.

Questions concerning the project or arranging a site visit with city staff should be directed to: Andy Lewis at 815-777-1050 or alewis@cityofgalena.org

RETURN THIS PAGE TO THE CITY OF GALENA

TABLE OF QUANTITIES – RFQ UNIT COSTS					
#	ITEM	UNIT	QUANTITY	UNIT COST \$	AMOUNT \$
1	Remove and replace 5-inch thick broom finish sidewalk	SF	50		
2	Remove and replace 5-inch thick exposed aggregate sidewalk	SF	50		
3	Install new 5-inch thick broom finish sidewalk	SF	50		
4	Install curb and gutter, 24-inch wide, 6-inch high	LF	50		
5	Remove and replace curb and gutter, 24 inches wide, 6-inch high	LF	50		
6	Remove and replace 9-inch thick concrete street, including epoxy coated dowels at 24-inch centers	SF	100		
	TOTAL COST				

All work to be completed in accordance with specifications described in this request for quotes.

Respectfully submitted:

Company

Date

Title

Signature

Address

APPROVED BY CITY OF GALENA

Signature

Date

GENERAL NOTES:

1. All locations for removal/replacement and new items will be marked by City Staff.
2. Unit cost for all new or replacement construction items will include for removal and disposal of all excavated material and site clearance of trees, branches and other debris.
3. New construction will match construction dimensions, type and style of existing surfaces on either side of area to be replaced. Unit cost will include for all saw-cutting of all hard surfaces to allow construction to adjacent surfaces.
4. Unit cost for curb/gutter will include for minimum of 8-inch thick aggregate base, epoxy coated ¾ inch steel dowels to adjoining curb and street at 24-inch centers, expansion material at start and finish and control joints to match street joints.
5. Unit cost for sidewalk will include for minimum of 6-inch thick aggregate base, with expansion material at start and finish, with troweled control joints to match existing.
6. Unit cost for sidewalk will include for adjusting valve boxes and all other utility covers.
7. Unit cost for curb/gutter and sidewalk will include for placing closed cell plastic expansion material to adjacent sidewalk, junction with curb/gutter, building property wall, around power poles and other utility features. Flowable sealant to be placed above expansion material where sidewalk is adjacent to a building wall.
8. Unit cost new or replacement sidewalk and thickened edge sidewalk will include for saw-cutting and removing strip of existing asphalt street (12-18 inches wide) and replacement with new hot mix asphalt to same thickness as existing street.
9. Unit cost for concrete street replacement will include for epoxy coated tie bars at 24-inch centers.
10. Removal item for sidewalks will include removal of steps and steel railings.
11. All concrete surfaces to be sealed with two coats of high solids sealer: Sil-Act ATS 190 LV or equal.
12. Contractor is to include all traffic management and control in their unit prices.
13. Contractor is to include for restoration of adjacent surfaces, including turf restoration, disturbed by the work in their unit prices, unless listed separately.
14. Refer also to all construction specifications listed in Request for Quotes.

TURF RESTORATION

This item is to include for provision of minimum of 4 inches of topsoil, grass seed, fertilizer and straw mulch. If sufficient topsoil is not recovered from the work site, it will be the contractor's responsibility to provide additional topsoil at no extra cost for this item. Unless otherwise noted this will be an included item.

ADDITIONAL WORK

All additional work to be in accordance with latest edition of IDOT Standard Specification for Road and Bridge Construction detailed in Section 109. No additional work can be completed without authorization from the City Engineer. Contractor will inform City immediately or within 24 hours of any proposed change to the contract. Payment will be agreed before additional work is completed and be based on unit prices, agreed lump sum or force account with hours agreed immediately or within 24 hours of proposed work. Force Account Form detailing the hours for labor and equipment is to be completed and submitted to City for approval within 24 hours of the proposed work being identified. When force account work is completed a breakdown of the labor, equipment and materials costs described in Section 109.04 is to be submitted to the City. No payment for the force account work will be authorized until the breakdown sheet is received and approved.