

Request for Quotes for Refurbishment of the Pergola at Grant Park

Instructions & General Information

The City of Galena is requesting quotes for refurbishing the concrete pergola at Grant Park as detailed below and also available at city website: www.cityofgalena.org under Departments/Engineering/Bid Documents.

Scope of Project

The City of Galena is requesting quotes to complete the work detailed below. All work to be in accordance with the latest versions of the International Building Code, Standard General Conditions of the Construction Contract and City Specifications

Conditions

1. All Work performed under this contract shall be subject to compliance with the Illinois Prevailing Wage Act, including the latest revisions and the Illinois Preference Act. Contractors are required to submit certified copies of their payroll.
2. The City of Galena shall be exempt from any liability for loss incurred by unsuccessful bidders in preparation for this proposal.
3. The City shall receive sealed quotes to complete the proposed work until:
10:00 AM, Tuesday 6th September 2016.
4. The City of Galena will make payment within thirty (30) days after acceptance of the work. The City of Galena reserves the right to reject any or all quotes.
5. Questions concerning the project or arranging a site visit with City Staff should be directed to: Andy Lewis at 815-777-1050 or alewis@cityofgalena.org

Specifications

1. Remove and reinstall two existing flood lights.
2. Carefully remove existing wire ties and loosen vines from support wires. Take care not to damage any of the vines.
3. Pressure wash entire pergola and use wire brush to remove organic staining. Take care not to damage any of the vines.
4. Repair all damaged areas of concrete, including filling of two abandoned electrical boxes, end beams, columns and bases, various chipped areas, capitals on two sides and tops of all beams. Deteriorated steel rebar to be cleaned of loose corrosion and treated with rust inhibitor **Sika FerroGard 903** or equal, applied in accordance with manufacturer's specification. Concrete to be repaired with **Sika Quick VOH** or equal applied in accordance with manufacturer's specification.
5. Apply two coats of **Sherwin Williams Loxon XP** or equal to entire pergola, applied in accordance with manufacturer's specification. Color to be white.
6. Replace support wires with plastic coated heavy gauge wire and reattach vines with plastic coated wire. Take care not to damage any of the vines.

General

1. Contractor is responsible for providing access to all work areas in accordance with recognized health and safety requirements.
2. Contractor is responsible for all clean-up at the end of the project and will ensure that all excess materials are removed from the site.

Attached Drawings include: None

Contractor to complete specified work at following prices:

TABLE OF QUANTITIES					
#	ITEM	UNIT	QUANTITY	UNIT COST \$	AMOUNT \$
1	Complete work to pergola as detailed	Sum	1		
	TOTAL				

All work to be completed in accordance with specifications described in this request for quotes.

The contractor is advised to visit the pergola at Grant Park to view the proposed work in order to determine the extent and nature of the listed work items.

Respectfully submitted:

Company

Date

Title

Signature

Address
APPROVED BY CITY OF GALENA

Signature

Date